

APPENDIX B

Permanent Bus Stop Requirements

Station	Description	Permanent Bus Terminal Requirements													
		Platforms (length)	Shelters ¹	Sidewalk/curb type	Lighting	Station signage	Route signage	Map Frame	Bike Racks ²	Waste bins	Benches	Emergency phones	CCTV cameras	Passenger Information Displays ³	Bus Lay-up
Gladstone	Eastbound bus stop, south side of Gladstone Ave, east of Trillium Pathway	18m	✓	SC11	✓	✓	✓	✓	x	✓	✓	x	x	✓	x
	Westbound bus stop, north side of Gladstone Ave, east of Trillium Pathway	18m	✓	SC11	✓	✓	✓	✓	x	✓	✓	x	x	✓	x
Carleton	Southbound platform, west side of Campus Ave, south of Library Rd	<i>No changes to platform anticipated</i>												✓ ⁴	
Walkley	Eastbound bus stop, south side of Walkley Ave, east of Airport Parkway ramp	18m	✓ ⁸	SC11	✓	✓	✓	✓	x	✓	✓	✓	✓	✓	x
Uplands	Westbound platform, north side of northernmost EY Centre access road, west of pick-up/drop-off roadway	53m	✓	Note ⁵	✓	✓	✓	✓	x	✓	✓	✓	✓	✓	X
Limebank	North side of station, Eastbound side of roadway, adjacent to Station Plaza ^{6 7}	2x18m; 2xx20m	✓ ⁸	SC11	✓	✓	✓	✓	x	✓	✓	✓	✓	✓	x
Limebank	North side of station, Westbound side of roadway, adjacent to Station Plaza ^{6 7}	2x18m; 3x20m	✓ ⁸	SC11	✓	✓	✓	✓	x	✓	✓	✓	✓	✓	x

¹ On-street bus stops shall be provided with a standard 5' x 10' shelter. On arterial corridors, a curved roof shelter is required.

² Bike racks shall be included in LRT station designs, therefore are not required at any permanent bus stops in close proximity to LRT stations.

³ Passenger Information Display infrastructure shall be moved by OC Transpo at no cost to Project Co, however DB Co shall provide the ducts/feeds to the bus stops at cost to Project Co

⁴ Project Co shall provide two lay-up spaces near Campus Ave, north of Library Rd

⁵ As per OC Transpo Transitway and Station Design Guidelines

⁶ Each Platform is route assigned, combining of platforms is not permitted

⁷ Project Co shall provide 5m maneuvering space between each Platform, all 20m Platforms shall be located between the 18m Platforms

⁸ Denotes existing shelter(s) to be relocated from existing Trillium Line Train Platforms by Project Co.